BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-01/2020-21 Dt:02-5-2020

APPROVED TENDER SCHEDULE –'B'

Item 08

Name of Work :-Providing and fixing missing kerb stones, covering slabs and desilting of drains at yelahanka old town and surrounding areas in kempegowda ward no-01 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri H S Prakash ( )	
				Rate	Rate in Words
1	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, with all lead and lift etc complete as per	Cum	262.67	285.00	Two Hundred EightyFive Only
2	KSRB 100-1 Loading and unloading of stone aggregates / sand/ kaner/ Moorum /soilKSRRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for hauled and return trip complete as per specification item No 17.1 page 117 and KSRB M.100.4.1 cost of haulage excluding loading and unloading MORTH to a distance of 4.00 K.M with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	262.67	78.00	SeventyEight Only
3	Supplying and fixing precast reinforced cement concrete slab 10 cm Thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc,. complete with all leads and lift conveyance charges labour charges inclusive of cost of all materials. (Drain covering slab)	Sqm	195.61	2103.00	Two Thousand One Hundred Three Only

	concrete kerb stones out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete as per direction of Engineer incharge.(P. No-27, I. No-5.30 of PW, P&IWTD SR 2018-19)	Nos	1834.88	389.00	Three Hundred EightyNine Only
5	KSSRB 800-1: Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 P. No-180, I. No-24.1	Sqm	825.70	76.00	SeventySix Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.